

ADMIRALTY SIGNAL ESTABLISHMENT

Specification AD/CV384/Issue 2. Dated 6.12.47. To be read in conjunction with K1001.	<table border="1"> <tr> <th colspan="2"><u>SECURITY</u></th></tr> <tr> <td>Specn.</td><td>Valve</td></tr> <tr> <td>Classified</td><td>Unclassified</td></tr> </table>	<u>SECURITY</u>		Specn.	Valve	Classified	Unclassified
<u>SECURITY</u>							
Specn.	Valve						
Classified	Unclassified						

→ Indicates a change.

<u>TYPE OF VALVE:-</u> Power Amplifier Triode.			<u>MARKING</u> See K1001/4.			
<u>CATHODE:-</u> Directly Heated.			<u>BASE</u> B4 See K1001/AIV/D5.1.			
<u>ENVELOPE:-</u> Glass.						
<u>PROTOTYPE:-</u> DET5.						
<u>RATING</u>		Note	Pin	Electrode		
Filament Voltage (V)	4.0		1	Anode		
Filament Current (A)	2.0		2	Grid		
Max. Anode Voltage (V)	600		3	Filament		
Max. Anode Dissipation(W)	25		4	Filament		
Mutual Conductance (mA/V)	7.5		<u>DIMENSIONS</u> See K1001/AI/D1.			
Amplification Factor	9.5		Dimension			Min.
Anode Resistance (Ω)	1270	A	A mm	-	170	
		A	B mm	-	67	
			<u>PACKAGING</u> See K1005.			
<u>NOTE</u> A. With $V_a = 100 \text{ V}$, $V_g = 0$.						

TESTS

To be performed in addition to those applicable in K1001

	Test Conditions				Test	Limits		No. Tested
	Vf (V)	Va (V)	Vg (V)	Ia (mA)		Min.	Max.	
a	4.0 A.C. or D.C.				If (A)	1.8	2.2	100% or S
b	4.0 A.C. or D.C.	400	Ad- justed	62.5	i. Vg (V)	-25	-36	100%
	For 10 mins. Vg to be checked every minute.				ii. Variation in Vg after 1st min. (V)	-	-2.0	100%
					iii. Reverse Ig at end of test (μA)	-	4.0	100%
c	4.0 A.C. or D.C.	400	+0.5	62.5	gm (mA/V)	5.0	10.0	100%
d	Valve to be run in stage 5 of the transmitter SWB8 for 15 minutes, under conditions of max. drive, i.e:-				<u>Operational Test.</u> Valve must operate satisfactorily and not deteriorate during the test.			100%
	Stage	Va (V)	Ia (mA)	Ig (mA)				
	4	450	76.0	5.4				
	5	450	60	60				