# Page 1 (No. of Pages 8 ) MINISTRY OF TECHNOLOGY - DLRD/RRE

## VALVE ELECTRONIC CV6223

Specification: Mintech. CV 6223 Issue 1 Dated May 1968. To be used in conjunction with K1001	SECURITY				
	Specification	<u>Valve</u>			
	Unclassified	Unclassified			

## Indicates change

TYPE OF VALVE:  CATHODE: ENVELOPE: PROTOTYPE	Power Travelling Wave Tube for Pulsed Operation in "S" Band Dispenser Glass enclosed within metal capsule giving pre-focused unit.	a		See K1001/4 Serial Number  BASE Special, designed to fit socket in mount
(N	atings and characterist ot for inspection Purpolimiting values are about the Non-simultaneous	MOUNTING POSITION  Axis Horizontal  CONNECTIONS		
Heater Voltage Max.Heater Curre Min. Operating R Min. High Level Min. Low Level G Min. Peak Power Max. Pulse Lengt Max. Duty Cycle Max. Negative Ca with respect and Collector Max. Peak Anode Max. Peak Helix Max. Mean Helix Max. Peak Cathod Nom. Magnetic Fi Min. Water Flow Max. Outlet Wate	ange (kMc/s) Gain (db) ain (db) Output (W) h (µSec) thode Voltage to Anode, Helix Strapped (kV) Current (A) Current (A) Current (A) Current (A) (Gauss) (litre/min.)	6.3±3% 3.0 2.7 to 3.3 26.0 250 20.0 0.005 7.5 0.20 0.25 1.00 1.5 800 1	A, F EBCE BCE E	(For pin reference see drawing page 7)  PIN ELECTRODE 1 Heater 2 Cathode/Heater 3 Anode 4 Helix Collector Connection by means of a flying lead  R.F. CONNECTIONS 50 ohms Co-axial Type C Connector  DIMENSIONS See Drawing Page 7

#### NOTES

- A. H.T. Voltages shall not be applied until at least three minutes after the application of the heater voltage.
- B. The pulse voltage is to be adjusted for optimum gain at 3.3 KMc/s. With this voltage and the specified coil current, the rated performance is available over the frequency range 2.7 3.3 KMc/s. For high level operation the voltage should be increased to that value stamped on the tube.
- C. The tube is to be operated in a mount (catalogue No. 5950-99-914-8096) in which the field is produced by a solenoid operating at  $21A \pm 0.5A$  under the conditions specified in the operating sheet supplied with each tube.
- D. The following are typical operating conditions optimised at 3.3 KMc/s with 250W peak output, and are intended as a guide to the user.

Pulse length:	15.0 µвес
P.R.F.	275 p.p.s.
v collector anode & helix:	0
V <sub>k</sub> :	-5.0 k♥
Icoll*	0.80 pk
Ihx	0.10A pk
I <sub>a</sub> :	0.01 pk
٧ <sub>f</sub> :	6.3V
I <sub>F</sub> :	1.0A
Isolenoid:	21.OA
Gain:	30 dB at 2.7 kMc/s 30 dB at 3.0 kMc/s 29 dB at 3.3 kMc/s

- E. The minimum operating range is that frequency range over which the rating values to which this note refers, may be obtained.
- F. If d.c. heater supplies are used, the positive end of the supply must be connected to the heater/cathode pin (pin 2).
- G. N. A. T. O. Stock Number 5960 99 037 5745

Page	3							V 0 2	- 2 3	_
				TESTS						
		Tests r	erformed in	addition to those appl	icabl	le in K	1001			
			Test Condi							
	V <sub>h</sub> tp P.R.F.			Solenoid current		Freq.	r.f. load			
	(∀)	(B4)	(p.p.s.)	(A)		(kMc/s	,	7.s.w.r.		
							r	not grea	ter	
	6.3	15.0	275	21.0		3.3	1	than 1.2	:1	
K1001	Test		Carrier and and and other access to the con-	Test Conditions	AQL	AQL Insp. % Level			Units	1
5J					%		Min.	Max.	***************************************	
		JP <u>A</u> Heater Curr	rent	V only Note 1		100%	७ <sup>.</sup> 1४ <del>०,०</del>	1.05	Amps.	Amer
	(b)	Focusing		Note 2		100%				
		(r.f. input I coll (peak	; <b>=</b> 0)				0.6	1.0	Amps.	
		I <sub>hx</sub> (peak)					_	0.12	Amps.	
		I (peak)					-	0.03	Amps.	
	(c)	Low level e	gain	Notes 3, 4, 6, 7 Pulse input voltage		100%	29•5 4•5	-	dB <b>k</b> ₹	
6.2	(a)	High level	gain	Notes 4,5a,5b,6,7 Pulse input voltage V (max).		100%	27.5	<b>-</b> 6.5	dB kV	
	(e)	Focusing		Frequency = 2700 Mc/s		100%		0.,		
		I <sub>coll</sub> (peak)		Notes 5a and 6		100,0	_	1.0	Amps.	
		I <sub>hx</sub> (peak)					_	0.20	Amps.	
		I (peak)					-	0.05	Amps.	
	(f) Spurious Oscillation (1)		cillation	Note 9 and 6		100%	No os shall detec		on 	
		(2)		Note 13 and 6	No oscillation shall be detended having a power amplitude greater than 1 mW peak, or tequivalent mean power.					d.

K1 001 5J	M	Test Conditions	AOL A	Insp.	LIMITS			
	Test				Min.	Max.	Units	
6.7	GROUP A Cont'd  (g) Match.  Input V.S.W.R.  Output V.S.W.R.	Notes 4, 10 Notes 4, 10		100%	•3		Ratio Ratio	
	(h) Water Head	At 1 litre/minute flow		100%	-	12.0	oms/Hg.	
	(i) Water pressure	At 100 lbs./sq. in. gauge for 2 minutes		100%	No leakage			
	(j) Capacitance, cathode to electrodes	To all electrodes strapped to capsule		100%	-	'2 <del>50</del>	p <b>P</b>	Ameti
	(k) Helix impedance	At 148.5 Mc/s + 2 Mc/s. Measured at helix input connection. Note 10, 12.		100%	-8 <b>+</b> <sub>o</sub>	-40 20	pF /mmhos	Arnelle,
	(1) Cold loss	At 3.0 kMc/s		100%	45	-	dВ	
GROUPS C, D and E omitted								
	GROUP F Life End Point 1000 hours Post Life Test High level gain	Wh = 6.3V d.c. Notes 11 and 14.  Conditions as in (a) t	o (h)	4,5%	25	-	dВ	
	GROUP G							
	(n) Electrical retest after 14 days holding period	Tests and limits as contained in tests (d) and (f) in Group A		100%	See G	roup A		

## notes

- 1. Read after five minutes
- 2. Set pulse input voltage to 5.5 kV.
- With an r.f. input of 8 mW, at 3.3kMc/s the pulse input EHT voltage is optimised
  to provide maximum output power.
- 4. Measurements shall be made at 100 Mc/s intervals over the range 2.7 3.3 kMc/s. However for those tests made for type approval purposes the measurements shall be made at 25 Mc/s intervals over the range.

- 5(a) The pulse input voltage shall be adjusted to give an optimum gain at an output of 250W.
- (b) The value of pulse input voltage for this condition shall be referred to in the specification as V<sub>O</sub> and shall be stamped on the tube.
- Measurements to be made in a standard mount approved by the R.R.E. Valve Authority.
- 7. The change in gain over any of the 100 Mc/s intervals referred to in Note 4 shall not exceed 2.5 dB.
- 8. H.T. voltages shall not be applied until at least three minutes after the application of the heater voltage.
- 9. The R.F. input shall be short circuited and the output load shall present a V.S.W.R. not less than 10:1 at 3 KMc/s. With the pulse input voltage at V max.
  +500V the load mismatch shall be varied through all phases. During these tests the output shall be observed with a matched crystal detector connected to a cathode ray oscilloscope whose combined sensitivity shall not be less than 5 mV per cm.

No spurious oscillations shall be detected.

- 10. No voltages shall be applied to the tube during this test.
- 11. The tube voltages shall be optimised for operation at a frequency of 3.3 kMc/s but during life the frequency of operation may be anywhere in the range 2.7 to 3.3 kMc/s. The output power shall be set at 250W ± 10%. The pulse length at 17.5 pS ± 5%. the p.r.f. at 265.0p.p.s± 2.5%. End of life shall be at 1000 hours or at that time when the high level gain is less than the given limit. The number of hours of life which a valve provides shall be recorded. Where the average life of five consecutive life tests provides a value less than 900 hours, the Valve Authority shall be informed and the cause of failure investigated.
- 12. This test shall be performed with the valve fitted into a test socket and approved by the Valve Authority in accordance with R.R.E. Drawing No. RRB 281204.
- 13. The R.F. input shall be short circuited and the output load shall be matched. The pulse input voltage shall be electronically swept at 50c/s through a range of ± 500 volts about V max, while the solenoid current is being varied manually between the limits of 20.5 and 21.5 amps. Alternatively the pulse input voltage may be manually swept through the above range for each of three values of solenoid current, 20.5,21.0 and 21.5 amps.

During these tests the output shall be monitored and either the peak or mean power of any oscillation measured as follows:-

- (a) For peak power, the output shall be measured, using a matched crystal detector connected to a cathode ray oscilloscope whose combined sensitivity shall be adequate for the measurement of 1 mW peak power. No oscillation having an amplitude greater than 1 mW peak shall be detected.
- (b) For mean power, a matched thermistor bridge having a full scale deflection of not more than 10 µW shall be used for measurement. A crystal detector connected to an oscilloscope may be used as an aid to observing oscillation.

### NOTES (Cont'd)


### 13 (cont'd)

It should be noted that a tube may not oscillate on each EHT voltage pulse nor for the full duration of that pulse.


When a mean power measurement is taken therefore, the voltage sweep shall be stopped at the point of maximum oscillation and the effective p.r.f. and width of r.f. pulse shall be measured to determine the correct duty cycle.

No oscillation shall be detected having an amplitude greater than the mean power equivalent to 1mW peak.

14 The positive end of the d.c. heater supply shall be connected to the heater/cathode connection.







ADVANCE COPY.

## ELECTRONIC VALVE SPECIFICATIONS

## SPECIFICATION Mintech/CV6223 Issue 1 Dated May 1968

## Amendment No.1

## Page 3. Tests Group A. (a) Heater Current

- (i) In the column headed Limits, Min. delete "0.9" and substitute "0.7".
- (ii) In the column headed Limits, Max. Delete "1.2" and substitute "1.0".

October 1969

R.R.E.

## SPECIFICATION MINTECH/CV6223, ISSUE 1, DATED MAY 1968

#### Amendment No 1

- Page 3 Test Clause (a) Heater Current
  - In the columns headed "LIMITS, Min and Max" -Delete "0.9" and "1.2"

Insert "0.75" and "1.05" respectively.

- 2 Page 4. Test Clause (j) Capacitance, cathode to electrodes

In the column headed "LIMITS, Max" -Delete "20" Insert "10"

3 Page 4. Test Clause (k), Helix impedance

> In the column headed "LIMITS, Min" -Delete "1" Insert "O"

#### ELECTRONIC VALVE SPECIFICATIONS

SPECIFICATION MINTECH/CV6223 ISSUE 1 DATED MAY 1968

AMENDMENT NO.2 (JULY 1976)

- 1 Page 1
  - (a) Delete Ministry of Technology DLRD/RRE

    Insert Ministry of Defence (PE) RSRE
  - (b) After Specification amend "Mintech" to read "MOD(PE)"
- 2 Page 4
  - (a) Group F. Amend end point to read 100 hours
  - (b) Delete "High level gain. Conditions as in (a) to (h) 25 (in minimum column) dB".

Insert in "Test Conditions" column:-

- "Tube to repass all Group AO 100% tests (b), (c), (d), (e), (f), (g), (k) and (l) same conditions and limits".
- (c) In Inspection level column, delete 4% insert 10%.
- 3 Page 5

Note 11

(a) Delete all text including and after "End of life shall be at 1000 hours etc."

Substitute "The test shall be terminated at the end of 100 hours and provided that the tube meets the Post Life test requirements it may be delivered. Where the average life of five consecutive life tests provides a value of less than 90 hours the Qualification Approval Authority shall be informed and the cause of failure investigated."